

Increasing productivity at Receiving and Sorting area with the implementation of an Automatic Sorter

Author: Aireen Valentín, Master of Engineering Management Program

Advisor: Dr. Héctor J. Cruzado, PE, Civil and Environmental Engineering Department



Abstract: The Sorting Department of the Distribution Center of a major chain of stores was too labor intensive, impacting safety, accuracy and production KPI's. After some minor processes improvement projects, the cost-benefit was not significant enough. Implementation of an Automated Sorter led to the re-engineering of the receiving and sorting processes. The velocity of freight flow to the shipping department improved said department's productivities. The projected annual savings are of \$937,359.

Introduction: Process improvement efforts were focused on the Sorting Department of the Distribution Center (DC) of a major chain of stores. After some minor improvement projects, it was evident that the cost-benefit was not significant enough to meet the business needs. Therefore, it was decided to pursue mechanization in the form of conveyors and an Automatic Sorter.

Problem: DC Sorting Department is considered the bottleneck of the operation due to its poor productivity capacity of **78 cases per man hour** and it's labor intensive nature, which impacted the **safety, accuracy** and **production KPI's**. Also, the area will not be able to support the store growth on the island. The goals are: increase sorting department productivity, support store growth on the island, reduce accidents by minimizing labor intensive task's and create a process driven accurate environment.

Methodology



- Receiving**
Unload pallets, label cases on REC dock, transfer onto empty pallet & haul pallet to sorting staging area.
- US Floor Loaded**
Manually unload freight onto individual store pallets.
- Processing**
Cases are placed onto carousel and sorted manually.

Figure 1: Old Process Flow

Design Criteria's:

- **FY16 Average Day, Peak Month** : Daily Volume and Sorter Throughput
- **Operation schedule:** 5 Days/ WK; 2 Shifts/Day
- **Volume by Store Formats and Distribution Channel Flow**
Format 1: 74%, Format 2: 20%, Format 3 : 6%
- **Optimal Staffing Model**
- **Store Counts** by format
- **Building Lay & Characteristics @ 130,000 sq/ft**

Table 1: Operational Capacity (manpower)

	Receiving	Sorting	Shipping
Associates/ Day	117	81	33
Cases / Day	>115,000	>105,000	>441,000




Figure 2: Actual Distribution Channel Flow

Old Building Layout & Operation




Figure 3: Old Building Layout



Figure 4: Old Receiving Process



Figure 5: US Floor Loaded



Figure 6: View from Old Sorting area

Actual Building Layout & Operation




Figure 7: Extensible to unload floor load



Figure 8: Receiving lines



Figure 9: Receiving process



Figure 10: Merge area




Figure 11: Scanner



Figure 12: Shipping lines

Installation Phase




Figure 13: Installation Phase Diagram

Installation Phase Duration

Phase 1: 15 Days
Phase 2: 7 Days
Phase 3: 8 Days
Phase 4: 3 Days
Phase 5: 4 Days
Total 37 Days




Figure 14: Productivities Graph

Saved hours: @16,000

Note: Saved hours are from 2 months

Objectives Results

- **Increased** Receiving CPMH in **27%**
- **Increased** Sorting CPMH in **58%**
- **Reduce** accidents from **3 LY vs. 0 TY**
- **Improve** process accuracy by **42%**

Other benefits

- **Increased** Shipping CPMH in **12%**
- **Increased** Total Building CPMH in **22%**
- **Reduce** DC Lead-time
- **Improve** associate morale
- **Decrease** non-conveyable freight

Conclusion: The implementation of an Automatic Sorter provided expected and unexpected benefits with a projection higher than the projected annual savings of **\$937,359**.

Future Work: Implement Phase 2 of the project in case that is required due to an increase of product centralization through the DC to avoid Direct to Store Deliveries.